



GENERAL NOTES:

1. ALL CONSTRUCTION WORK SHALL BE IN ACCORDANCE WITH AUS-SPEC SPECIFICATIONS 0319 AUXILIARY CONCRETE WORKS, 0136 GENERAL REQUIREMENTS, 0161 QUALITY MANAGEMENT, 1112 EARTHWORKS AND 1141 FLEXIBLE PAVEMENT BASE AND SUBBASE.
2. DIMENSIONS IN MILLIMETERS UNLESS STATED OTHERWISE.
3. THE CONTRACTOR SHALL NOTIFY COUNCIL'S OFFICER A MINIMUM OF 48 HOURS PRIOR TO PLACING CONCRETE TO INSPECT FORMWORK, LEVELS AND REINFORCEMENT.
4. STRENGTH OF CONCRETE TO BE  $f'_c = 32\text{MPa}$  WITH COVE TROWEL FINISH.
5. CONCRETE SHALL BE CURED FOR 7 DAYS AS PER SPECIFICATION.
6. GRADE OF PITCH ASSUMES THAT THE CENTRE OF THE OVAL FALLS AWAY EVENLY. FOR OVALS WITH DIFFERENT SLOPES THE GRADE OF THE PITCH MAY BE ALTERED AFTER APPROVAL FROM COUNCIL. IN SUCH CASES THE MAXIMUM GRADE OF THE PITCH SHALL BE 1% AND THE MINIMUM GRADE OF THE PITCH SHALL BE 0.35%.
7. CRICKET PITCH TO BE 28m LONG, 2.8m WIDE AND MINIMUM 125mm THICK WITH 50mm LONGITUDINAL FALL FROM THE CENTRE OF SLAB TO EACH RUN UP. STUMP HOLES TO BE BOXED OUT. REINFORCEMENT TO BE SL82 WITH 200mm OVERLAP AND A MINIMUM 50mm COVER.
8. GRASS SURROUNDING PITCH TO BE ROLLED OUT TURF MATCHING EXISTING GRASS SPECIES, ENSURE GRASS IS FLUSH WITH TOP OF SLAB AND SLOPES AWAY FROM PITCH AT MINIMUM 1%, MAXIMUM 4% IN ALL DIRECTIONS FOR THE DISTANCES SPECIFIED IN THE DRAWING.
9. SYNTHETIC GRASS TO BE SHORT PILE HEIGHT (9-11mm) LAID OVER THE TOTAL LENGTH AND WIDTH IN TWO HALVES WITH HOLES FOR THE STUMP BOXES A MINIMUM 14 DAYS AFTER CURING OF CONCRETE. CREASES TO BE MARKED AS SHOWN IN WHITE.
10. SUB-BASE TO BE CRUSHED ROCK COMPACTED TO 95% STANDARD COMPACTION EXTENDED 150mm MINIMUM OUT FROM SLAB ON ALL SIDES.
11. FOR SUB-GRADE CBR > 5, SUB-BASE TO BE 100mm THICK. FOR SUB-GRADE CBR ≤ 5, SUB-BASE TO BE 150mm THICK.
12. SLAB IS INTENTIONALLY DESIGNED TO CRACK LIGHTLY ALTHOUGH IT WILL BE COVERED BY SYNTHETIC TURF.

TURFING NOTES:

1. PREPARATION: REMOVE ANY EXISTING TURF, WEEDS, RUBBISH, STONES OR DEBRIS FROM AREA TO BE TURFED.
2. TOPSOIL: ALL TOPSOIL SHALL COMPLY WITH AS4419 'SOILS FOR LANDSCAPING AND GARDEN USE'. TOPSOIL SHALL BE A SOIL BLEND WITH A MAXIMUM 20% SCREENED COMPOSTED ORGANIC MATTER. HYDRAULIC CONDUCTIVITY TO BE 15-30 cm/hr. pH RANGE TO BE 5-6.5. AFTER APPROVAL OF THE PROPOSED TOPSOIL, DEPOSIT AND SPREAD TOPSOIL TO ACHIEVE A MINIMUM OF 50mm THICKNESS TO ALL DISTURBED AREAS FOR TURFING AFTER SLAB CONSTRUCTION.
3. TURFING: TURF SHALL BE 'COUCH' (SANTA ANA) UNLESS OTHERWISE DIRECTED BY LANDSCAPE ARCHITECT. TURF SHALL BE 'A' GRADE, TYPICAL OF THE SPECIES, FREE FROM ALL PESTS, DISEASES, WEEDS, AND OTHER PLANT MATTER. TURF SHALL BE GUARANTEED FREE FROM 'NUT GRASS' (CYPERUS ROTUNDUS). TURF SHALL BE CUT TO A MINIMUM 25mm THICK IN LONG 300mm WIDE STRIPS.
4. LAYING: LAY PIECES OF TURF IN STRAIGHT LINES RUNNING PERPENDICULAR TO THE SLOPE, WITH CROSS-JOINTS STAGGERED AND CLOSE BUTTING. LAY TURF WITH AN EVEN GRADIENT, FREE FROM LUMPS AND DEPRESSIONS AND NOT ABLE TO POND WATER. ENSURE THAT NEW TURF FINISHES FLUSH WITH EXISTING TURF. TAMP DOWN WELL AND FILL ALL JOINTS WITH TOP DRESSING. TOP DRESSING IS TO BE PIT SAND TO COMPLY WITH AS4419. SPREAD SAND EVENLY OVER SURFACE OF GRASS IN LAYERS OF NOT MORE THAN 10mm. DO NOT BURY GRASS.
5. TOP DRESSING: WHEN TURFED AREAS HAVE BECOME ESTABLISHED AND IMMEDIATELY AFTER THE FIRST CUT, TOP DRESS TURF WITH 10mm LAYER OF TOP DRESSING TO AS4419. DO NOT TOP DRESS DURING WINTER MONTHS UNLESS DIRECTED BY COUNCIL OFFICER. TURF TO BE LAYED WITH TOP OF TOP DRESSED GRASS LEVEL WITH TOP OF CONCRETE
6. PROTECTION: ALL TURF SHALL BE PROTECTED FROM TRAMPLING BY THE ERECTION OF BARRIERS. CONTRACTOR IS TO PROVIDE ADEQUATE FIRST WATERING OF TURF.

					DRAWN ....KC.. SCALE AS SHOWN SHEET SIZE: <b>A3</b>	APPROVED  GROUP MANAGER INFRASTRUCTURE SERVICES D.L.	<b>WINGECARRIBEE SHIRE COUNCIL</b>				
							<b>STANDARD DRAWING CRICKET PITCH NOTES</b>				
A	ORIGINAL ISSUE	KC	25/01/21					DATE: 25/01/2021	PLAN No: SD162B	SHEET 2 OF 2	ISSUE <b>A</b>
ISSUE	AMENDMENTS	DRAWN	DATE								